


1009-07	
REVISIONS	
ADDED ADDITIONAL 1/4" 20 HOLES	1
3/10/84	2
CHGD. NOTES 6, 7 & LOCK BRACKET. ADDED NOTE 8	3
J.L.L. 6-17-85	
A. MILLER 3/19/18	
ADDED NOTE 9.	
D.E. 3/19/18	



NOTES:

1. THE CABINET SHALL BE OF NO. 10 U.S.S. GAUGE, AND THE BACK PLATE OF NO. 12 U.S.S. GAUGE SHEET STEEL.
2. UNLESS OTHERWISE SPECIFIED TOLERANCE ON HORIZONTAL TAPPED HOLES TO BE ±.010", AND ARE TO HAVE AT LEAST THREE COMPLETE THREADS.
3. ALL STEEL SURFACES SHALL HAVE A PROTECTIVE COATING OF GRAY ENAMEL, A.C. HORN CO. NO. 1614, SHERWIN-WILLIAMS CO. NO. 18076, OR DEVCO & REYNOLDS CO. NO. 21.
4. CABINET DOOR SHALL BE PROVIDED WITH CATCH AND FACILITIES TO ACCOMMODATE STANDARD SEALS AND PADLOCK WITH 5/16" DIA. HASP.
5. THE EQUIPMENT SHALL MEET THE REQUIREMENTS OF THE NATIONAL BOARD OF FIRE UNDERWRITERS, AND THE DEPARTMENT OF PUBLIC WORKS OF THE CITY OF NEW YORK.
6. HIGHFIELD LOCK RECEPTACLE WITH SEAL FERRULE, CAT. NO. 9338900, HIGHFIELD MFG. CO., BRIDGEPORT, CONN. OR BROOKS BARREL LOCK GUARD CAT. NO. 86505, E.J. BROOKS CO., NEWARK, N.J. THE LOCKING DEVICE AND LOCK BRACKET SHALL BE PROPERLY ALIGNED TO RECEIVE A UTILITY BARREL LOCK.
7. SAMPLES OF THE CABINET SHALL BE SUBMITTED TO THE DISTRIBUTION INSTRUMENTATION ENGINEER FOR APPROVAL.
8. A NAMEPLATE SHALL BE ON THE OUTSIDE OF THE ENCLOSURE AND CONTAIN MANUFACTURER'S NAME AND CATALOG NO.
9. NO TOTALIZERS SHALL BE ISSUED FOR NEW INSTALLATIONS. THIS SPECIFICATIONS IS FOR REFERENCE OF EXISTING EQUIPMENT, INSTALLATION OF WIRELESS EQUIPMENT & POWER TRANSFER RELAYS INSTALLATIONS.

FIELD MANUALS
NO. 4. SERV. INSTL.
NO. 16. SERV. INSTL.
NO. 18. SERV. INSTL.
NO. 19. SERV. INSTL.
NO. 20. SERV. INSTL.

MOUNTING EQUIPMENT 14" X 25 1/2" FOR DEMAND METERING DEVICES

CONSOLIDATED EDISON COMPANY OF N. Y., INC.
ELECTRICAL ENGINEERING DEPT.

DATE 10-26-82 SPEC. NO. 108-A REV. 3
LAST REV. 3/19/18

REV.	DATE	BY	CHKD. BY	DATE
1	10-26-82	W. J. B.	W. J. B.	10-26-82
2	3/19/18	A. M.	A. M.	3/19/18
3				
4				
5				
6				
7				
8				
9				
10				