EO-16830-B

REVISIONS

Charles Fisher 10/18/88	2
REARRANGED BILL OF MATERIAL TO DATE V.D. 11-28-87	
ROY WILLIAMS.	3
UPDATED DWG. ADDED NOTE h C.W 11/27/95	
M. BALDWIN 4/7/99	4
UPDATED DWG. ADDED NOTES i & J C.W 4/7/99	

ITEM NO.	DESCRIPTION	STOCK NO.	LOW PRESSURE INSTL. SIZE	HIGH PRESSURE INSTL. SIZE		SPEC. OR DWG. NO.
21	PLUG, METER NUT (FOR TESTING) 20LT	339-0655	X	X	X	—
20	HARDWARE FOR MOUNTING BRACKET:					
	MASONRY WALL:					
	ANCHOR SELF DRILLING, 1/4-20 (2 REQ.)	038-1525	X	X	X	—
	BOLT, ROUND HEAD, STEEL, 1/4-20 x 1" (2 REQ.)	036-1485	X	X	X	—
	WASHER STEEL, 1/4" (2 REQ.)	038-0444	X	X	X	—
	FRAME TYPE WALLS:					
	BOLT, TOGGLE, ROUND HEAD, STEEL, 1/4-20 x 4 (2 REQ.)	035-2237	X	X	X	—
	WASHER, STEEL, 1/4" (2 REQ.)	038-0444	X	X	X	—
19	NIPPLE, STEEL, TON 1 1/2" x 6"	330-1215	X	X	X	ASTM A-53 GR. B
18	TEE, 150 LB. 1 1/2"	332-1478	X	X	X	ANSI B16.3
17	NIPPLE, STEEL 1 1/2" x 12"	330-3484	X	X	X	ASTM A-53 GR. B
16	PREFABRICATED METER SET ASSEMBLY FOR THREE METERS WITH MOUNTING BRACKET	339-0184	X	X	X	CON. ED. G-75
15	HEADER, VERTICAL, STEEL, TOE 1 1/2" x 1 1/2" x 1 1/2"	339-0473	X	X	X	CON. ED. G-72
14	CAULKING COMPOUND, WATERPROOF	—	X	X	X	—
13	WALL SLEEVE SCH. 40 SIZE AS REQUIRED	—	X	X	X	—
12	VALVE, PLUG WHERE REQUIRED BY LOCAL MUNICIPLITY, SIZE AS REQUIRED	—	X	X	X	*
11	PIPE STEEL					
	1"	320-1753	—	X	X	ASTM A-53 GR. B
	1 1/2"	320-1779	X	—	—	
10	ELBOW, 90°, 150LB.					
	1" x 1"	332-0983	—	X	X	ANSI B16.3
	ELBOW, 90°, RED., 150LB. 1 1/2" x 1"	332-1288	X	—	—	
9	NIPPLE, STEEL 1" x 2"	330-2742	X	X	X	ASTM A-53 GR. B
8	PREFABRICATED METER SET ASSEMBLY FOR TWO METERS WITH MOUNTING BRACKET	339-0176	X	X	X	CON. ED. G-73
7	CAP, 150 LB. 1 1/2"	332-7707	X	X	X	ANSI B16.3
6	NIPPLE STEEL 1" x 5"	330-0936	—	X	X	ASTM A-53
	NIPPLE STEEL, REDUCING 1" x 3/4" x 7"	330-4441	—	X	X	GR. B
5	METER ELBOW, 90°, STL., TON. 1 1/2" x 8" x 8"	339-0481	X	X	X	ASTM A-53 GR. B
4	COUPLING, 150 LB. 1 1/2"	332-8226	X	X	X	—
	COUPLING, REDUCING 1 1/2" x 1 1/4"	337-0608	X	—	X	*
	1 1/2" x 1"	337-2588	—	X	—	*
	UNION, 150 LB. 1 1/2"	332-6048	X	—	—	—
3	NIPPLE, STEEL 1 1/4" x 4" THD. ONE END	330-1058	X	—	—	ASTM A-53
	1" x 3" THD. ONE END	330-0878	—	X	X	GR. B
	1 1/2" x 2 1/2"	330-3286	X	—	—	
2	GAS SERVICE REGULATOR	—	—	1" x 1" x 3/4"	1" x 1 1/4" x 1"	PROCEDURE G-48
1	GAS METER	—	250 TC	250 TC	250 TC	
	NUMBER OF UNITS	—	2-6	2-4	5-6	—

FOR INSTALLATION DWG. SEE EO-16726-B SHEET 1 OF 2

* SEE "REQUIREMENTS FOR GAS SERVICE INSTALLATIONS" BOOKLET.

INSTALLATION OF 2 TO 6 UNIT PREFABRICATED METER SETS FOR OUTDOOR CLASS 250TC METERS BILL OF MATERIAL

CONSOLIDATED EDISON COMPANY OF N. Y., INC.
CENTRAL GAS OPERATIONS DEPT.

DATE 2-25-86
LAST REV. 4/7/99

DWG. NO. EO-16830-B REV. 4
SHEET 2 OF 2

METERING SPECIFICATION AND PROCEDURE VOLUME NO. 3

MAILING LIST 3

NO.	DATE	REVISIONS	APPROVED

FOR APPROVAL

DIV.	SIGNATURE	DATE

DRAWN BY H.E. MARK 2-25-86 DATE
CHECKED BY DATE
TRACED BY DATE
SCALE
APPROVED
GAS ENGINEER DATE
MANAGER DATE