

DATE	02-25-86	DWG.	EO-16726-A	REV.	12
LAST REV.	08-17-21	NO			

8-97291-03

REVISIONS

G. LUDWIG 0

CREATED
SHEET 2
TRANSFERRED
BILL OF MAT'L
INFO. FROM
EO-16830
ADDED ITEM 22
C.P. 10-30-06

SEE SHEET 1
FOR CHANGES

G. LUDWIG 8

REVISED TO
CHANGE
EFFECTIVE DATE
(SEE SHEET 1)
K.M. 05-14-19

G. LUDWIG 9

REVISED
MATERIAL LIST
ITEMS 23 & 24
C.S. 01-20-20

G. LUDWIG 10

ADDED ITEMS
25 & 26 ON
SHEET 1 & 2.

D.O. 03-24-21

G. LUDWIG 11

REVERTED BACK
TO REVISION
NO. 9.

D.O. 04-13-21

G. LUDWIG 12

ADDED DETAIL B
ADDED ITEM 25,
NOTE M ON
SHEET 1 &
ITEM 25 ON
SHEET 2.

D.O. 08-17-21

METERING
SPECIFICATIONS
& PROCEDURES
VOLUME NO. 3

ITEM NO.	DESCRIPTION	STOCK NO.	LOW PRESSURE INSTL. SIZE	HIGH PRESSURE INSTL. SIZE		SPEC. OR DWG. NO.
1	GAS METER NUMBER OF UNITS		250TC 2-6	250TC 2-4	250TC 5-6	
2	GAS SERVICE REGULATOR			1" x 1" x 3/4"	1" x 1 1/4" x 1"	G-48
3	NIPPLE, STEEL 1 1/4" x 4" TOE 1" x 3" TOE 1 1/2" x 2 1/2"	330-1058 330-0878 330-3286	X X	 X 	 X 	ASTM A-53 GR. B
4	COUPLING COMPRESSION, INSULATING, 1 1/2" COUPLING COMPRESSION, REDUCING, INSULATING, 1 1/2" TO 1 1/4" COUPLING COMPRESSION, REDUCING, INSULATING, 1 1/2" TO 1"	337-3776 337-0608 337-7777	X X 	X X	X X 	* * *
5	METER ELBOW, 90°, STL., TOE 1 1/2" x 8" x 8"	339-0481	X	X	X	ASTM A-53 GR. B
6	NIPPLE STEEL 1" x 5" NIPPLE STEEL, REDUCING 1" x 3/4" x 7"	330-0936 330-4441	 	X X	X X	ASTM A-53 GR. B
7	CAP, 150 LB. MI, 150 LB 1 1/2"	332-7707	X	X	X	ANSI B16.3
8	PREFABRICATED METER SET ASSEMBLY FOR TWO METERS WITH MOUNTING BRACKET	339-0176	X	X	X	CON ED G-73
9	NIPPLE, STEEL 1" x 2"	330-2742	X	X	X	ASTM A-53 GR. B
10	ELBOW, 90°, MI, 150 LB. 1" x 1" ELBOW, 90°, RED., MI, 150 LB. 1 1/2" x 1"	332-0983 332-1288	 X	X 	X 	ANSI B16.3
11	PIPE STEEL, BLACK 1" 1 1/2"	320-1753 320-1779	 X	X 	X 	ASTM A-53 GR. B
12	VALVE, PLUG WHERE REQUIRED BY LOCAL MUNICIPALITY, SIZE AS REQUIRED		X	X	X	*
13	WALL SLEEVE SCH.40 SIZE AS REQUIRED TA-VALVE OR		X	X	X	
14	CAULKING COMPOUND, WATERPROOF		X	X	X	
15	HEADER, VERTICAL, STEEL, TOE 1 1/2" x 1 1/2" x 1 1/2"	339-0473	X	X	X	CON ED G-72
16	PREFABRICATED METER SET ASSEMBLY FOR THREE METERS WITH MOUNTING BRACKET	339-0184	X	X	X	CON ED G-75
17	NIPPLE, STEEL 1 1/2" x 12"	330-3484	X	X	X	ASTM A-53 GR. B
18	TEE, 150 LB. MI, 150 LB 1 1/2"	332-1478	X	X	X	ANSI B16.3
19	NIPPLE, STEEL, TOE 1 1/2" x 6"	330-1215	X	X	X	ASTM A-53 GR. B
20	HARDWARE FOR MOUNTING BRACKET: MASONRY WALL: ANCHOR SELF DRILLING, 1/4 - 20 (2 REQ'D.) BOLT, ROUND HEAD, STEEL, 1/4 - 20 x 1 (2 REQ'D.) WASHER, STEEL, 1/4" (2 REQ'D.) FRAME TYPE WALLS: BOLT, TOGGLE, ROUND HEAD, STL, 1/4 - 20 x 4 (2 REQ'D.) WASHER STEEL, 1/4" (2 REQ'D.)	038-1525 036-1485 038-0444 035-2237 038-0444	X X X X X	X X X X X	X X X X X	
21	PLUG, METER NUT (FOR TESTING) 20 LT	339-0655	X	X	X	
22	COUPLING, MI 150 LB 1 1/2"	332-8226	X	X	X	ANSI B16.3
23	LOCK WING STOP, 1"		X	X	X	*
24	A.Y. McDONALD 6312-FFE-W 1"x1"x1" BYPASS BAR (FOR CLASS 250 TC), 1" STRAIGHT SWIVELS (PART OF BYPASS BAR ASSEMBLY)		X	X	X	*
25	1 INCH F X M NPT TA-VALVE OR 1 INCH M X M NPT TA-VALVE WITH 1 INCH M X F BELL COUPLING, BLACK MALLABLE IRON.	3771916		X	X	

FOR INSTALLATION DWG. SEE EO-16726 SHT. 1 OF 2
* SEE REQUIREMENTS FOR GAS SERVICE INSTALLATIONS" BOOKLET.

INSTALLATION OF 2 TO 6 UNIT
PREFABRICATED METER SETS FOR
OUTDOOR CLASS 250TC METERS
BILL OF MATERIAL
SHEET 2 OF 2

CONSOLIDATED EDISON COMPANY of N.Y., INC.
GAS ENGINEERING DEPT.

DATE 02-25-86 DWG. EO-16726-B REV. 12
LAST REV. 08-17-21 NO SHEET 2 OF 2